



GENERAL NOTES

1. BASE ANGLE (STANDARD BASE CONDITION) FURNISHED IN 20'-0" STANDARD LENGTHS. BASE ANGLE SHOULD BE OMITTED AT OVERHEAD DOORS, PERSONNEL DOORS, AND FRAMED OPENINGS. BASE ANGLE SHOULD BE ATTACHED WITH NAILINGS SUPPLIED BY MANUFACTURER.
2. C.I.P. (OPTIONAL), FURNISHED IN 10'-0" LENGTHS BY MANUFACTURER, MUST BE ORDERED FOR SHIPMENT PRIOR TO POURING FOUNDATION. OMIT C.I.P. AT OVERHEAD DOORS, BUT RUN CONTINUOUSLY AT PERSONNEL DOORS. ATTACH C.I.P. USING COMMON 6d NAILS PURCHASED LOCALLY.
3. BASE GIRT (OPTIONAL) FURNISHED CONTINUOUS BETWEEN COLUMNS, MUST BE FIELD CUT AT PERSONNEL DOORS AND ALL FIELD LOCATED FRAMED OPENINGS.
4. BASE CHANNEL, USED WITH INTERIOR LINER PANELS, WILL BE FURNISHED IN REQUIRED LENGTHS BUT SOME MODIFICATIONS MAY BE REQUIRED. OMIT BASE CHANNEL AT OVERHEAD DOORS, AND PERSONNEL DOORS. ATTACH BASE CHANNEL USING NAILINGS PROVIDED BY MANUFACTURER.
5. INSIDE CLOSURE (STANDARD) FURNISHED IN 3'-0" LENGTHS AT PERIMETER OF BUILDING AT ALL BASE CONDITIONS. OMIT CLOSURE AT OVERHEAD DOORS, PERSONNEL DOORS, AND WHEN BUILDING IS INSULATED.
6. IN ORDER TO MAINTAIN THE WARRANTY, THE WALL PANELS MUST NOT TOUCH THE BOTTOM OF THE SHEETING NOTCH.

 P.O. BOX 130819 • TYLER, TEXAS 75713	ERECTION STANDARDS	DRAWING ES-110
	CONDITIONS AT BASE	